Summit Exterior Group
135 NW 9th, Portland, Oregon
971-720-8445
summitexteriorsgr.com
Oregon CCB #251474

A Northwest Valley Construction company | Licensed and insured through Northwest Valley Construction

Protecting your most expensive asset from the ground up. Real People. Reliable Home Improvement.

Estimate: Fence, Site Work and Flooring

Prepared for
Todd and Mackenzie Sprague
35520 Lower Loop Rd, Pacific City, Oregon
907-300-3111 | 503-351-5858

Estimate details
Estimate date: October 20, 2026
Expires: October 31, 2026
Contractor license: Oregon CCB #251474

Project overview

Summit Exterior Group will build about 190' of 5' tall cedar and black hog wire fence, with two 4' gates, and a 14' black steel handrail, for Todd and Mackenzie Sprague. We will also remove an 8' x 23' paver area and restore it with clean fill dirt and new sod, and build a 2-step tiered paver area, 3' wide and 6' long, from the reused pavers and sand. Inside, we will prepare the floor and install 752 square feet of Harvey Maria Luxury Northmore Fired Terracotta (Special) flooring with the Ardex glue system. For the in-law suite, we will insulate and soundproof the main wall and replace the door.

The finished fence has cedar-framed panels with black welded wire, cedar-wrapped posts, and black gate hardware.

Scope of work and process

This is a hands-on, built-in-place fence. Every panel is cut, assembled and fitted on site, and the posts are set in concrete. By the numbers: about 190 linear feet, 28 posts, 25 panels, 2 gates, and roughly 110 bags of concrete (about 4.4 tons) mixed and poured.

1. Planning and preparation — $499.00

- Call 811 so underground utilities are marked before any digging.
- Confirm the property lines with the customer, then stake the fence line and mark every post location.
- Measure the ground along each run, since two sides climb about 11 feet over 60 feet, and plan the panel sizes to fit.
- Order and receive all materials.

2. Posts and concrete footings — $5,611.00

- Dig 24 holes for line posts, 12" wide and about 36" deep, and 4 larger holes for the gate posts, 16" wide and about 40" deep.
- Spread 4" of gravel in each hole for drainage.
- Cut each pressure-treated post to length and brush preservative on the cut ends.
- Wrap the buried part of each post in a waterproof barrier that extends above the ground line.
- Set each post plumb, brace it, and pour concrete around it. Slope the top of each footing so water runs away from the post.
- Let the concrete cure before any weight goes on the posts.

3. Building the panels — $9,392.00

- Cut cedar 2x4s into rails and uprights for 25 panels.
- Cut a groove along the top and bottom rails to hold the wire, and drill small drain holes in the bottom groove so water can't collect.
- Cut the black welded wire to size and seal every cut end against rust.
- Assemble each panel: seat the wire in the grooves, fasten the uprights with stainless screws, and back it up with stainless staples.
- On the two sloped sides, build the panels as angled frames so they follow the slope of the ground.

4. Hanging the panels — $2,311.00

- Fasten a small cedar cleat to each post to hold the panel at the right height.
- Set each panel on its cleats, check that it is level, and screw it to the posts with three heavy stainless screws at each end.
- Work along each run so the spacing and height stay even.

5. Post wrap and caps — $2,717.00

- Wrap all 28 posts in cedar on all four sides, stopping above the ground so the wood can drain and dry.
- Fit each wrap tight against the panels, then finish every post with a cedar cap.

6. Gates — $737.88

- Build two 4' wide cedar and wire gates with a heavier frame and a diagonal brace so they don't sag.
- Hang each gate on heavy 6x6 posts with black heavy-duty hinges.
- Install a black latch and a gate stop on each gate, then adjust until it swings and latches cleanly.

7. Handrail — $1,003.00

- Build a 14' handrail from round steel tubing, cut to length and welded together by our crew.
- Grind the welds smooth, then clean, prime and paint the whole handrail black with a rust-resistant exterior paint.
- Mount the handrail securely at the location agreed with the customer, and touch up the paint where needed.

8. Paver removal and sod — $2,044.00

- Lift and remove the pavers from the 8' x 23' area (about 184 square feet), setting aside the pavers needed for the new paver steps and hauling away the rest.
- Remove the paving sand underneath and save what is needed for the new paver steps.

- Fill and level the area with clean fill dirt, compacted so it settles evenly.
- Lay new sod over the area and water it in.

9. Tiered paver steps — $650.00

- Mark out a 3' wide by 6' long area and excavate it so the steps sit on solid ground.
- Build a 2-step tiered paver area from the reused pavers, bedded in the saved paving sand.
- Level and tighten each tier, then sweep sand into the joints so the pavers stay locked in place.

10. Flooring preparation and installation — $11,340.00

- Grind down the existing bolts sticking out of the floor so the surface is smooth and flat.
- Pour self-leveling compound in the areas of concern to bring the floor level.
- Roll on a quick-dry moisture barrier over the prepared floor.
- Install 752 square feet of Harvey Maria Luxury Northmore Fired Terracotta (Special) flooring, 54 cases, using the Ardex glue system.

11. In-law suite soundproofing — $799.00

- Drill 4" access holes in the main wall so the cavity can be filled with insulation.
- Insulate the main wall, then spray a cellulose-fiber sound-deadening product up and down the walls. It goes on like spray foam, but it is made of cellulose fibers.
- Replace the door.
- Seal the gaps with backer rod filler to help soundproof the room.

12. Cleanup and walkthrough — $699.00

- Haul away debris and excess soil.
- Walk the finished fence with the customer and fix anything they point out.

Materials used

Everything below is included in the price.

Category	Materials
Posts	24 pressure-treated 4x4 ground-contact line posts and 4 pressure-treated 6x6 gate posts, 10' long
Footings	About 110 bags of 80 lb concrete mix and about 25 bags of drainage gravel
Wire	28 sheets of black 6-gauge welded hog wire, 4" x 4" openings, galvanized and dip-coated
Panel frames	Cedar 2x4s for 25 panels and 2 gates, plus 2x2 cedar cleats
Post wrap and caps	Cedar boards to wrap 28 posts on all four sides, and 28 cedar post caps
Gate hardware	4 heavy-duty black hinges, 2 black latches and 2 gate stops
Fasteners	Stainless structural screws, stainless deck screws and stainless staples
Protection	Waterproof wrap for buried post sections, wood preservative for cut ends, and rust-protection spray for cut wire
Handrail	14' of round steel tubing and fittings, welding supplies, metal primer and black rust-resistant paint, and mounting hardware
Flooring	54 cases of Harvey Maria Luxury Northmore Fired Terracotta (Special) flooring for 752 square feet, the Ardex glue system, self-leveling compound, and quick-dry moisture barrier
In-law suite	Cellulose-fiber sound-deadening spray product, replacement door, and backer rod filler for sealing
Paver area	Clean fill dirt and sod to cover about 184 square feet, with disposal of the leftover pavers and paving sand; the new paver steps reuse the removed pavers and sand

Total price

Total, including all materials, labor and delivery for the work described above **$37,802.88**

Deposit to schedule and order materials
$15,244.46

Balance due in full on the day of completion
$22,558.42

Price by step	Price
1. Planning and preparation	$499.00
2. Posts and concrete footings	$5,611.00
3. Building the panels	$9,392.00
4. Hanging the panels	$2,311.00
5. Post wrap and caps	$2,717.00
6. Gates	$737.88
7. Handrail	$1,003.00
8. Paver removal and sod	$2,044.00
9. Tiered paver steps	$650.00
10. Flooring preparation and installation	$11,340.00
11. In-law suite soundproofing	$799.00
12. Cleanup and walkthrough	$699.00
Total	**$37,802.88**

The deposit covers materials, shipping, delivery and ordering. Payments made by credit card carry a 5% fee per transaction.

Assumptions and terms

- **Property lines:** the customer confirms the property lines before work begins.
- **Not included:** removal of an existing fence, trees or stumps, rock or bedrock digging, and a survey.
- **Permits:** fences under 7' generally need no state building permit, but local zoning rules apply; we will confirm with Tillamook County before digging.
- **Schedule:** the start date depends on when materials arrive and will be confirmed in writing.
- **Warranty:** the fence carries a 15-year contractor's warranty on workmanship.
- **Estimate expiration:** this estimate is valid through October 31, 2026.
- **Changes:** any change to the work above requires a signed change order, and the full amount of the change must be paid when it is signed.

Acceptance

By signing, the customer accepts this estimate and agrees to the price and terms above.

Customer signature	Printed name	Date
Summit Exterior Group representative	Printed name	Date