Summit Exterior Group
135 NW 9th, Portland, Oregon
971-396-3033
summitexteriorsgr.com
Oregon/Washington CCB #251474

A Northwest Valley Construction company | Licensed and insured through Northwest Valley Construction

Estimate: Exterior Painting

Prepared for

Sherry Rodriguez
113 2nd Ave, Oakville, Washington 98568
Phone: 518-348-4525

Estimate details

Estimate date: October 23, 2026
Expires: November 2, 2026
Contractor: Summit Exterior Group

Project overview

Summit Exterior Group will repaint the exterior of the home and the detached garage at 113 2nd Ave in Oakville, in a dark grey Sherwin-Williams color. The work includes minor dry rot repairs around the trim and door frames, and sealing all exposed joints on the existing old cedar siding with Vulkem caulking before painting.

The home	Two stories, about 1,364 sq ft of living space, built in 1900, with old cedar siding
Siding to be painted	About 2,600 sq ft in all: the house about 1,900 sq ft and the detached garage about 700 sq ft
Windows and doors	About 14 windows (12 on the house, 2 on the garage), plus all entry doors and the garage door
Paint color	Sherwin-Williams Iron Ore, SW 7069, a popular dark grey

Measurements and counts are estimates from property records and will be confirmed at the walkthrough before work begins.

Scope of work and process

1. Preparation and cleaning — $1,755.00

- Cover landscaping, walkways and anything near the walls.
- Wash the siding and trim to remove dirt, mildew and chalking, then let it dry fully.
- Scrape off all loose and peeling paint and sand the edges and rough areas smooth.
- Spot-prime all bare wood.

2. Minor dry rot repairs — $850.00

- Probe the trim and door frames for soft or rotted wood.
- Cut out the damaged areas and rebuild them with new wood or exterior wood filler, then sand and prime.
- This is an allowance for minor repairs. If we find larger rot, we show you and give you a price before doing any extra work.

3. Vulkem caulking on the cedar siding — $790.00

- Seal all exposed joints on the old cedar siding with Vulkem polyurethane sealant: butt joints, corners, trim and siding connections, and around windows, doors and wall openings.
- Tool each bead smooth so water runs off, not into the wall.
- Let the sealant cure as the manufacturer directs before any paint goes over it.

4. Priming and painting the house — $3,270.00

- Mask windows, glass and hardware.
- Prime the repaired and bare areas, using a stain-blocking primer on bare cedar to stop wood stains from bleeding through.
- Apply two finish coats of Sherwin-Williams exterior paint in Iron Ore (SW 7069) to the siding.
- Paint the trim, doors and window frames in the colors you choose, confirmed in writing before we start.

5. Detached garage — $1,145.00

- Clean, scrape, sand, repair, caulk, prime and paint the garage siding, trim and doors the same way as the house, in the same colors.

6. Cleanup and walkthrough — Included

- Remove masking and coverings, and pick up all debris.
- Walk the finished job with you and touch up anything you point out.

Materials used

Everything below is included in the price.

Category	Materials
Paint	Sherwin-Williams exterior acrylic paint, Iron Ore (SW 7069), for the siding, plus paint for the trim and doors in the colors you choose
Primer	Exterior primer, including a stain-blocking primer for bare cedar
Sealant	Vulkem polyurethane sealant for all exposed siding joints
Repairs	New exterior wood and exterior wood filler for minor dry rot repairs
Prep and protection	Cleaner, scrapers, sandpaper, masking, plastic and drop cloths

Total price

Total, including all materials and labor for the work described above, house and detached garage **$7,810.00**

Deposit to schedule and order materials
$3,905.00

Balance due in full on the day of completion
$3,905.00

The deposit covers materials, ordering and scheduling. Payments made by credit card carry a 5% fee per transaction.

Assumptions and terms

- **Older home:** this home was built in 1900, and paint on homes built before 1978 may contain lead. Lead-safe testing and work practices required by law apply, and any added cost is quoted to you before work starts.
- **Not included:** repairs beyond the minor dry rot allowance, siding replacement, window or door replacement, and painting of porch floors, decks, fences or the foundation.
- **Weather:** exterior painting needs dry weather, so the schedule moves with the forecast and will be confirmed in writing.
- **Exterior paint warranty:** 10 to 15 years on the finished paint, covering peeling, flaking and blistering caused by our workmanship or by defective materials. It does not cover damage from new rot or water leaks, impact, or areas outside the work described above.
- **Estimate expiration:** this estimate is valid through November 2, 2026.
- **Changes:** any change to the work above requires a signed change order, and the full amount of the change must be paid when it is signed.

Acceptance

By signing, the customer accepts this estimate and agrees to the price and terms above.

Customer signature	Printed name	Date
Summit Exterior Group representative	Printed name	Date